



- NOTE:
1. ALL CLEANOUT MATERIAL TO BE SAME AS CARRIER PIPE.
 2. CLEANOUT TO BE PLACED 12" FROM BACK OF SIDEWALK.
 3. BEDDING MATERIAL TO BE COMPACTED 3/4"-0 CRUSHED ROCK

<p>The selection and use of this Standard Drawing, while designed in accordance with generally accepted engineering principles and practices, is the sole responsibility of the user and should not be used without consulting a Registered Professional Engineer.</p>	
<p>NOTE: All material and workmanship shall be in accordance with the current Oregon Standard Specifications</p>	<p>2002</p>
<p>OREGON STANDARD DRAWINGS</p> <p>CITY OF HOOD RIVER</p> <p>SANITARY SEWER CLEANOUT</p>	<p>REVISIONS</p> <p>DESCRIPTION</p> <p>City of Hood River Modifications</p>
<p>DATE</p> <p>12-02</p>	<p>2002</p>